


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 8 Twp. 11S Rge. 19 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Frontier Oil Company  
Lease Name Giinther Well No. 1  
Office Address 536 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-17 19 55  
Application for plugging filed 12-17 19 55  
Application for plugging approved 12-17 19 55  
Plugging commenced 12-17 19 55  
Plugging completed 12-17 19 55  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	159.44'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 1/2 sk hulls, 15  
sx cement, mud to 40'; Plug  
with 1/2 sk hulls, cement to  
surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Company  
Address 505 Orpheum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle (Employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
536 Petroleum Bldg., Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 19 55

My commission expires 11-17-58.

Notary Public.

12-30-1955

15-051-00957-00-00

CONTRACTOR'S WELL LOG

COMPANY:	Frontier Oil Company
CONTRACTOR:	Leben Drilling Company
FARM:	Ginther #1
LOCATION:	SE SE SW Sec. 8-11-19 Ellis County, Kansas
COMMENCED:	December 8, 1955
COMPLETED:	December 17, 1955

Ø	159	Surface soil
159	966	Shale
966	1116	Dakota Sand
1116	1275	Shale, redbed
1275	1438	Shale
1438	1484	Anhydrite
1484	1800	Shale, lime, shells
1800	2115	Shale
2115	2465	Lime, shale
2465	2657	Shale, lime
2657	2751	Lime, shale
2751	3004	Shale, lime
3004	3138	Lime, shale
3138	3266	Shale, lime
3266	3325	Lime, shale
3325	3336	Heebner
3336	3347	Shale
3347	3360	Brown Lime
3360	3388	Lantz
3388	3555	Lime
3555	3637	Lime, shale
3637	3651	Lime
3651	3800	Conglomerate
	<u>3800</u>	<u>Rotary Total Depth, D &amp; A</u>

Set 8 joints of 8 5/8" surface casing @ 159.44 feet.

I, George A. Angle, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ginther #1, SE SE SW Section 8-11-19, Ellis County, Kansas, as reflected by the files of the Leben Drilling Company.

*George A. Angle*  
 \_\_\_\_\_  
 George A. Angle

STATE OF KANSAS            )  
 COUNTY OF SEDGWICK    ) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 29th day of December, 1955.

*Melvin Head*  
 \_\_\_\_\_  
 Notary Public

My commission expires November 17, 1958

12-30-1955  
 CONSUL GENERAL  
 Wichita, Kansas