

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-051-25,138-0000

LEASE NAME Greathouse

WELL NUMBER 7

1,060 Ft. from S Section Line

2,290 Ft. from E Section Line

SEC. 19 TWP. 11 RGE. 19 (S or W)

COUNTY Ellis

Date Well Completed 6-14-02

Plugging Commenced 6-14-02

Plugging Completed 6-14-02

RECEIVED  
6-21-2002  
JUN 21 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

15-051-25138-00-00

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., PO Box 709, Russell, KS 67665

PHONE (785) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-14-02 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	218'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each saw. Push bridge plug to 3,670', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,475', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 750', pump 100 sax cement on plug thru drill pipe. Push plug to 270', pump 40 sax cement on plug. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Oil Producers, Inc. License No. 5184

Address Shields Bldg., PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., PO Box 709  
Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 19th day of June, 2002

My Commission Expires: \_\_\_\_\_



Ruth Phillips  
Notary Public

OR




Shields 15-051-25138-00-00  
Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.  
Well: Greathouse #7  
Commenced: June 7, 2002  
Completed: June 15, 2002  
Contractor: Shields Oil Producers, Inc.

Well Description: Approx. NW SW SE  
Sec. 19-11S-19W  
Ellis County, KS



CASING RECORD

Size	Run	Pulled
8 5/8"	218'	Cmtd. w/165 sax

Elevation: 2,090' KB  
Treatment:  
Production: D & A  
Tops:

RECEIVED  
6-21-2002  
JUN 21 2002  
KCC WICHITA

..... Figures Indicate Bottom of Formations .....

Rock & shale	221'
Sand & shale	1,460'
Anhydrite	1,500'
Shale	2,876'
Shale & lime	3,167'
Lime	3,312'
Lime & shale	3,479'
Lime	3,675'
Lime & shale	3,688'
Arubuckle	3,700'

Notes