

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 11 Twp. 11S Rge. (E) 19(W)

Location as "NE/CNW/SW" or footage from lines. NE NW SE

Lease Owner J. A. Allison et al

Lease Name VINE Well No. 1

Office Address 1528 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 16, 1966

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced December 16, 1966

Plugging completed December 16, 1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey)



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3585 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|---------|------------|
| | Surface | 0 | 212" | 8-5/8" | 12/9/66 | ---- |
| | Casing | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 540 feet; Plug and 25 sacks Cement thru the Drill Pipe; Heavy Mud to 200 feet; Plug and 20 sacks Cement thru the Drill Pipe; Mud to 40 feet; 1/2 sack Hulls and Plug with 8 sacks Cement to Base of Cellar; 2 sacks Cement in Rat Hole. Job completed at 3:00 A.M.

RECEIVED
DEC 21 1966
12-21-1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Lawrence F. Gray of Sage Drilling Co (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of December 1966

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970

15-051-30405-00-00

DRILLERS LOG

VINE NO. 1

| | | | |
|-----------------------------------|-------------|---------------------|---|
| CASING RECORD: | COMPANY: | J. A. Allison et al | DESCRIPTION: |
| 8-5/8" @ 212' w/150 sax cement | CONTRACTOR: | Sage Drilling Co. | NE NW SE Sec. 11-11S-19W Ellis County, Kansas |
| TOTAL DEPTH: 3585' | COMMENCED: | December 9, 1966 | |
| | COMPLETED: | December 16, 1966 | |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|------------------|-------------|-----------|----------------|
| Surface Soil | 0 | 213 | |
| Shale | 213 | 435 | |
| Sand | 435 | 468 | |
| Red Bed | 468 | 560 | |
| Sand | 560 | 574 | |
| Shale | 574 | 774 | |
| Sand | 774 | 981 | |
| Shale | 981 | 1328 | |
| Anhydrite | 1328 | 1363 | |
| Shale & Lime | 1363 | 1820 | |
| Lime & Shale | 1820 | 3189 | |
| Lime | 3189 | 3408 | |
| Lime & Shale | 3408 | 3467 | |
| Conglomerate | 3467 | 3565 | |
| Lime | 3565 | 3585 | |

RECEIVED
STATE CORPORATION COMMISSION
12-21-1966
DEC 21 1966
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

BY Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 20th day of December, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.