

15-195-20227-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-2-1972
AUG 2 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center Building, Wichita, Kansas.

Lease Name McCall Well No. 1

Location SW-SW-NE Sec. 6 Twp. 11 Rge. (E) (W) 22

County Trego Total Depth 3990'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #400, Duncan, Oklahoma. License No.

Operation Completed: Hour 5:15 AM Day 31 Month 7 Year 1972

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 550'.

Circulated hole with heavy mud. Pulled DP to 775' and displaced 110 Cu. Ft. cement
thru DP from 775' to 450'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru DP.
Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Fehel
Well Plugging Supervisor

INVOICED
DATE 8/3/72
INV. NO. 6109-u