

15-195-00016-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO: \_\_\_\_\_

LOCATION NW NW NE

SEC. 7 TWP. 11 RGE. 22

Dry Hole  \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Kircheck

Operator Prime Drilling Co. & Drains Corp. Address 1516 Liberty Bank Bldg  
Oklahoma City, Okla

Field \_\_\_\_\_ County Trego

Total Depth 3942 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3922'

100 sax cement behind.

Baker plugs to 3524', top perforations at 3500'.

Filled with sand to 3490', set 5csax cement with dump bailer,

Pulled 3238' 5 1/2", filled with mud to 250', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
7-14-1952  
JUL 14 1952  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 7 T 11 R 22  
BOOK PAGE 29 LINE 45 Date \_\_\_\_\_

*John P. ...*  
District Conservation Agent  
7-9-52