

15-065-20417-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. 32, Victoria, Kansas.

Lease Name Butcher Well No. B-2

Location W/2-NE-SE Sec. 32 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 4035'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No. _____

Operation Completed: Hour 4:00 PM Day 1 Month 2 Year 1974

The above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 150 Sx.
1029'--4 1/2" Production casing cemented on bottom with 175 Sx. No plug-back indicated.
Top perforations from 3954' to 3957'.

Pushed plug to 3850', sanded well back to 3800' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1128') and squeezed well initially with 5 sacks hulls and 7 sacks gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15 sacks gel from 825' to 200' and followed with 30 Cu. Ft. cement from 200' to 125' then 3 sacks gel from 125' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure--500#. Final shut-in pressure 150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *K. S. DeChels*
Well Plugging Supervisor

DATE 2/5/74

INV. NO. 8501-W