

15-195-20281-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1974
6-21-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F & M Oil Co., Inc.

Complete Address 603 Union Center Wichita, Kansas

Lease Name Kraemer Well No. 1

Location NW NW Sec. 11 Twp. 11 Rge. (E) (W) 22

County Trego Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12:45 P Day 9 Month 6 Year 1974

The above well was plugged as follows:

RTD 3900' 8 5/8 csg set at 218' cwc 150 sk. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 225' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Massey
Well Plugging Supervisor

INVOICED

DATE 6/21/74

INV. NO. 9356-W