

15-195-00384-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1960
6-22-1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Trego
Location: Se - Se NW Sec. 20 Twp. 11 Rgs. 22 (E) _____ (W) _____
Name of Field: _____ Total Depth: 4016

I have this date completed supervision of plugging of:

Lease Name: Lemke Well No. 1

Operator's Full Name: John O Farmer

Complete Address: Russell Kans.

Plugging Contractor: Knights Casing Pulling

Address: Chase Kans. License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 6 PM Day 10 Month June Year 1960

The above well was plugged as follows:

TD - 4016 - 8 5/8 - 160 - 5 1/2 - 4016 - BB to 3992 - Prg - 3884
Sand to 3870' and dumped 4 sack cement with dump
bar. Shot pipe at 3400 and pulled same to 600
ft and circulated hole with gel mud to top followed
by 20 sack cement, pulled pipe to 160' and displaced
20 sack mud, pulled pipe out of hole, built solid
rock bridge at 40 ft and topped with 10 sack cement

Signed: Gilbert P. Leiper
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 6/24/60
NO. 1535-W