

15-195-0115-00-00

CP-3

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
4-16-1963
APR 16 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bergman Drilling Co.,

Complete Address: 425 Union Center, Wichita, Kansas.

Lease Name Hixson Well No. 1

Location CNW-NW Sec. 30 Twp. 11 Rge. (E) (W)22

County Trego Total Depth 3960

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:00P Day 14 Month 4 Year 1963

The Above well was plugged as follows:

227'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx

cement thru DP. Heavy mud to 220' set plug and 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40' set plug with 1/2 sack

hulls and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/16/63

INV. NO. 6911-W

Signed: W. L. Nichols
Well Plugging Supervisor