

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County Sec. 27 Twp. 11S Rge. 22 E/W
Location as "NE/CNW/SW" or footage from lines
SE SE SE

Lease Owner Foxfire Oil & Gas

Lease Name Shubert Well No. #1

Office Address 1103 Douglas Bldg. Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed October 20 19 80

Application for plugging filed October 20 19 80

Application for plugging approved October 20 19 80

Plugging commenced October 20, 3:30 A.M. 19 80

Plugging completed October 20, 5:00 A.M. 19 80

Reason for abandonment of well or producing formation
No Commercial Production

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation Depth to top Bottom Tl. Depth of Well

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface casing	common	0	293.94'	8 5/8"	293.94'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 @ 600' with 50 sxs

Plug #2 @ 300' with 30 sxs

Plug #3 @ 40' with 10 sxs to cellar

5 sxs in rathole

cemented with 50-50 poz 4% gel

plugdown @ 5:00 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Company, Inc.

308 West Mill Plainville, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

Donald C. Marchant (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.


(Signature) Donald C. Marchant

(Address) 1103 Douglas Bldg., Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 24 day of October, 19 80

My commission expires 4/6/84

Notary Public



15-195-20702-00-00

WELL LOG

OPERATOR: Foxfire Oil & Gas

WELL NAME: Shubert #1 LOCATION: SE SE SE 27-11S-22W

COUNTY: Trego STATE: Kansas

WELL COMMENCED: October 9, 1980 WELL COMPLETED: October 20, 1980

ELEVATION: 2351' K.B. TOTAL DEPTH: 4074'

PRODUCTION: D & A RIG NO: #1

CASING - 8 5/8": 293.94' of used 28# cemented with 120 sxs common 2% gel 3% cc cement circ
5 1/2": none

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	301'			
301'	819'	sand and shale		
819'	1190'	shales and sands	1190 - 1 3/4 degrees	
1190'	1338'	shale and sands		
1338'	1517'	shale and sand		
1517'	1789'	shales and sands		
1789'	1856'	shale	1856 - 1 1/2 degrees	
1856'	2110'	shale		
2110'	2450'	shales and limes		
2450'	2797'	shale and lime		
2797'	3038'	shale and lime		
3038'	3066'	shales and limes	3066' - 3/4 degree	
3066'	3290'	shale and lime		
3290'	3424'	lime and shale		
3424'	3521'	lime and shale		
3521'	3524'	lime		
3524'	3578'	lime		
3578'	3654'	lime and shale		
3654'	3709'	lime and shale		
3709'	3709'			
3709'	3718'	lime and shale		
3718'	3794'	lime		
3794'	3875'	lime		
3875'	3875'		3875' - 1 degree	
3875'	3892'			
3892'	3992'	lime and shale		
3992'	4030'	lime and chert		
4030'	4074'	lime and chert		
4074'	RTD			

STATE OF KANSAS
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief the above facts are true and correct

RECEIVED
STATE CORPORATION COMMISSION
11-26-1980
NOV 26 1980
CONSERVATION DIVISION
Wichita, Kansas

PIONEER DRILLING CO., INC.
By Connie J. Austin

SUBSCRIBED AND SWORN TO, BEFORE ME, This 23 day of October, 1980

BERNADETTE GARDNER
STATE NOTARY PUBLIC
ROCKS COUNTY, KS.
My App. Exp. 5/7/83
KANSAS

Bernadette Gardner
NOTARY PUBLIC