

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Perkins Oil Enterprises, Inc.
Address: P.O. Box 707, Howard, Ks. 67349
Phone: (620) 3742133 Operator License #: 4448
Type of Well: oil Docket #: -
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-24-2008 (Date)
by: Duane Sims (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 2543 Bottom: 2600 T.D. 2600
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-049-20,409-0000
Lease Name: Hyde
Well Number: 20
Spot Location (QQQQ): SW - SE - SW -
330 Feet from North / South Section Line
3630 Feet from East / West Section Line
Sec. 9 Twp. 30 S. R. 9 East West
County: Elk
Date Well Completed: 10-28-1976
Plugging Commenced: 11-30-08
Plugging Completed: 12-4-08

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss lime	oil	2599	surf	4 1/2"	2600	605'
		150	surf	8 5/8"	150'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" to 1535, spotted 10 sack cement and gel, shot off casing at 605 pulled casing, ran 535' 2" and cement well to surface.

34203 KCC
RECEIVED
MAR 12 2009
KCC WICHITA

Name of Plugging Contractor: Kevin Wardlow, Pirate well Service License #: 5241
Address: 747 E. Jefferson, Howard, Ks. 67349
Name of Party Responsible for Plugging Fees: Perkins Oil Enterprises, Inc.
State of Kansas County, Elk, ss.

James R. Perkins (Employee of Operator) or (Operator) on above-described well, being first duly affirmed
That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Box 707, Howard, Ks. 67349

affirmed
SUBSCRIBED and SWORN TO before me this 11 day of March, 2009
Rene L. Triboulet My Commission Expires: 8-8-09
Notary Public

[Handwritten initials]



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 227780

Invoice Date: 12/04/2008 Terms:

Page 1

PERKINS OIL ENTERPRISES
P.O. BOX 707
HOWARD KS 67349
(620)374-2133

HYDE #20
18577
120108

Part Number	Description	Qty	Unit Price	Total
1104	CLASS "A" CEMENT	17860.00	.1500	2679.00
1118B	PREMIUM GEL / BENTONITE	400.00	.1700	68.00
1107A	PHENOSEAL (M) 40# BAG)	120.00	1.1500	138.00
1123	CITY WATER	4000.00	.0140	56.00

Description	Hours	Unit Price	Total
418 P & A NEW WELL	1.00	925.00	925.00
418 EQUIPMENT MILEAGE (ONE WAY)	75.00	3.65	273.75
T-35 WATER TRANSPORT (CEMENT)	5.00	112.00	560.00
486 MIN. BULK DELIVERY	1.00	315.00	315.00

RECEIVED
DEC 06 2008

BY:.....



RECEIVED
MAR 12 2009
KCC WICHITA

Parts:	2941.00	Freight:	.00	Tax:	185.28	AR	5200.03
Labor:	.00	Misc:	.00	Total:	5200.03		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____

WF



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 18577
LOCATION B-welle
FOREMAN Coop

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-1-08	6470	Hyde #20				EIK
CUSTOMER Perkins Oil			TRUCK #			
MAILING ADDRESS			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE			TRUCK #			
			DRIVER			

JOB TYPE PTA HOLE SIZE 8 1/2 HOLE DEPTH 500' CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Cemented 500' to surface through 2 3/4 tubing w 190 lbs cement

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405N	1	PUMP CHARGE		925.00
5406	25	MILEAGE		223.25
5407	1	Bulk Truck		315.00
55D1C	5hr	Transport		560.00
1104	17,860 #	Cement		2679.00
1118B	400 #	Gel		68.00
1102A	120 #	Pheno Seal		138.00
1123	4000 gal	Cx by Water		56.00
				RECEIVED
				MAR 12 2009
				KCC WICHITA
				SALES TAX
				185.28
				ESTIMATED TOTAL
				\$5200.03

Ravin 3737

AUTHORIZATION [Signature] TITLE # 227780 DATE _____



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 227723

Invoice Date: 11/30/2008 Terms:

Page 1

PERKINS OIL ENTERPRISES
P.O. BOX 707
HOWARD KS 67349
(620)374-2133

HYDE #20
18594
11/26/08

Part Number	Description	Qty	Unit Price	Total
1104	CLASS "A" CEMENT	940.00	.1500	141.00
1118B	PREMIUM GEL / BENTONITE	350.00	.1700	59.50
1123	CITY WATER	4620.00	.0140	64.68

Description	Hours	Unit Price	Total
398 CEMENT PUMP	1.00	925.00	925.00
398 EQUIPMENT MILEAGE (ONE WAY)	50.00	3.65	182.50
T-64 WATER TRANSPORT (CEMENT)	6.00	112.00	672.00
486 MIN. BULK DELIVERY	1.00	315.00	315.00

RECEIVED
DEC 04 2008

BY:.....

RECEIVED

MAR 12 2009

KCC WICHITA

Parts:	265.18	Freight:	.00	Tax:	16.70	AR	2376.38
Labor:	.00	Misc:	.00	Total:	2376.38		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 18594
LOCATION Bathesville, OK
FOREMAN Kirk Sanders

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-26-08	6470	Hyde 20				FIK
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <u>Peckins Oil</u>			398	John		
			486	Jake		
			403 764	James K.		
CITY		STATE	ZIP CODE			

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2
 CASING DEPTH _____ DRILL PIPE _____ TUBING 1" down to 537' OTHER _____
 SLURRY WEIGHT 15.6 SLURRY VOL 1.18 WATER gal/sk 5.2 CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Rig ran 1" down to 1000' & washed down last 537'. Ran gel spacer & 100' bottom plug & dispa. Shut down & washed up.


ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE (Plug)		925.00
5406	50	MILEAGE		182.50
5407	1	Bulk Trk		315.00
5501C	6 hrs.	transport		672.00
1104	10 sk / 940 #	Cement (Class A)	*	141.00
1118B	7 sk / 350 #	Premium Gel	*	59.50
1123	110.661 / 4620 gal	City Water	*	64.68
RECEIVED				
MAR 12 2009				
KCC WICHITA				
			6.3% GST	SALES TAX
				ESTIMATED
				TOTAL
				16.70
				2,376.39

Ravin 3737

AUTHORIZATION [Signature]

TITLE _____
227723

DATE _____



Invoice

Pirate Well Service, LLC.
 PO Box 7
 747 E. Jefferson St.
 Howard, KS 67349

Date 12/1/2008
 Invoice # 142

Cell 620-330-3666
 Home 620-374-2301
 Fax 620-374-2301
 kwardlow@sktc.net

Bill To
 Perkins Oil
 Jim Perkins
 P.O. Box 707
 Howard, KS 67349

Terms Net 15

Due Date 12/16/2008

Description	Hours	Rate	Amount
(plug well) 11/25/08 drive to well rig up run 1" pipe to about 1400', pull 5 jts back out try to run back in to get pass plug, Lay out 20 jts. 11/26/08 Run in 17jts & wash down 7 more. Had 49jts in hole, pull 1 out, just about got hung in hole. Pipe at 1535' ran gal spacer & 10 sacks cement (100' cement). Lay out 1" pipe dug out around well to get to bowl & slips. Try to pull 4 1/2 casing got about 5" pull. 12/1/08 rig up to pull casing shot off 605' & pull pipe. Run in 535' 2 /38 tubing & cemented, pull out tubing & top off well. Rig down & move.	17.5	125.00	2,187.50T
Load 1" pipe take trailer to well, go to Sedan & get 1" elevators. take trailer back to yard & unload 1" & load 2 3/8 tubing take to well. when finish take trailer back to yard with 2 3/8 & 4 1/2 on it.	6	80.00	480.00T
Pipe Dope		8.00	8.00T
tong usage	2	25.00	50.00T
Consulting Fee	3	35.00	105.00T
Hyde 20			

Subtotal \$2,830.50
Sales Tax (6.3%) \$178.32
Total \$3,008.82

Make check payable to
 Kevin Wardlow

Balance Due \$3,008.82

Thank you for
 your business

RECEIVED
 MAR 12 2009
 KCC WICHITA

CORNISH WIRELINE SERVICES, INC.

P.O. DRAWER H • CHANUTE, KANSAS 66720

620-431-9308

INVOICE

SOLD TO: PERKINS OIL ENTERPRISES, INC.
c/o JIM PERKINS
R.R. #2, BOX 707
HOWARD, KANSAS 67349

Date of Invoice 12-4-08

Invoice # 14515

PLEASE RETURN ONE COPY OF INVOICE WITH PAYMENT.

DATE OF SERVICE	TYPE OF SERVICE	AMOUNT
12-1-08	<p>HYDE NO. 20 ELK COUNTY, KANSAS</p> <p>SHOT OFF 4-1/2" PIPE AT 600' WITH 1/3# BLOCK OF HDP</p> <p style="text-align: center;">RECEIVED DEC 06 2008</p> <p>BY:..... ✓</p> <p style="text-align: center;">THANK YOU. WE APPRECIATE YOUR BUSINESS!!</p> <p>TERMS: All invoices are due in full 30 days after invoice date. A FINANCE CHARGE of 1 3/4% (21% per annum) will be assessed after 30 days.</p>	\$400.00

RECEIVED
MAR 12 2009
KCC WICHITA