

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Wilton Petroleum, Inc  
Address: P O Box 391  
Phone: ( 620 ) 628 - 4466 Operator License #: 7775  
Type of Well: D & A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 2-26-09 (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 135248690000  
Lease Name: Bieber  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - SE - NE - SE  
1819 Feet from  North /  South Section Line  
524 Feet from  East /  West Section Line  
Sec. 28 Twp. 20 S. R. 21  East  West  
County: Ness  
Date Well Completed: 12-24-08  
Plugging Commenced: 3-04-09  
Plugging Completed: 3-04-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss	Water	Surface	222'	8 5/8"	222'	0
		Surface	4462'	5 1/2"	4462'	2240'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled 2240' of casing, loaded 5 sxs of sand, set bridge plug w/2 sxs of sand above perms, loaded hole w/ mud, 50 sxs @1480', 60 sxs @620', 50 sxs @240', 10 sxs @ 40' filled the hole w/ concrete

Name of Plugging Contractor: H & D OilField Services, Inc. License #: 32970  
Address: P O Box 87 Bazine, KS 67516

Name of Party Responsible for Plugging Fees: Wilton Petroleum, Inc  
State of Kansas County, McPherson, ss.

Bernie Rundstrom (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 391 Canton KS 62428

SUBSCRIBED and SWORN TO before me this 11 day of March, 2009



Mary Jane Lauer My Commission Expires: 4-4-09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

MAR 12 2009

KCC WICHITA

[Signature]



CHARGE TO: WILTON PETROLEUM

ADDRESS

CITY, STATE, ZIP CODE

TICKET  
No 15379

PAGE 1 OF 1

SERVICE LOCATIONS 1. <u>HAWS</u>	WELL/PROJECT NO. <u>2</u>	LEASE <u>BLEEDER - 2</u>	COUNTY/PARISH <u>NESS</u>	STATE <u>KS</u>	CITY	DATE <u>03-04-09</u>	OWNER
2. <u>NESS</u>	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <u>H/D Well</u>	SHIPPED VIA <u>CT</u>	DELIVERED TO <u>3E. 12 1/2, WILTON BAZINE</u>	ORDER NO.	
3.	WELL TYPE <u>OIL</u>	WELL CATEGORY <u>ABANDON</u>	JOB PURPOSE <u>PTA</u>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF		QTY.	UM	QTY.	UM	
575		1			MILEAGE #112	30	mi	5	00	150 00
576P		1			Pump Service	1	EA	750	00	750 00
290		1			DAIR	2	CHL	35	00	70 00
328		2			60-40pore 4% GEL	180	SK	9	00	1620 00
581		2			SERVICE CHCCMT	180	SK	1	50	270 00
583		2			DRAYAGE	226.53	Tm	1	00	226 53
288		2			20-40 SAND	15	SK	22	00	330 00

RECEIVED  
 MAR 12 2009  
 KCC WICHITA

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X

DATE SIGNED 03-04-09 TIME SIGNED 1100  A.M.  P.M.

**REMIT PAYMENT TO:**  
  
**SWIFT SERVICES, INC.**  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

<b>SURVEY</b>	AGREE	UN-DECIDED	DIS-AGREE
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?			
WE UNDERSTOOD AND MET YOUR NEEDS?			
OUR SERVICE WAS PERFORMED WITHOUT DELAY?			
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?			
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES <input type="checkbox"/> NO		
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND			

PAGE TOTAL	3416	53
TAX	181	08
TOTAL	3597	61

**CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES** The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR DAVASH APPROVAL

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 03-04-09 PAGE NO. 1

CUSTOMER WILTON PETROLEUM WELL NO. 2 LEASE BIEBER JOB TYPE PTA TICKET NO. 15379

CHART NO.	TIME	RATE (BPM)	VOLUME (BB) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1100							ON LOCATION FREE POINT CMT 180 60-40 4% gel, 15 SXS SAND 5 1/2" TD 4460, SHUTOFF @ 2240
	1230							PULL 5 1/2" UP TO 1420
	1430	4.0	0		✓		100	START CMT
			13.0		✓		50	END CMT 50 SXS @ 1480
			0		✓		50	START DISP
			26		-		150	CATCH CMT
			18		-		200	CIRC MUD
	1440		20		✓		200	END PULL 5 1/2" TO 620 FT
	1608	4.0	0		✓		100	START CMT
			15.8		✓		200	END 50 SXS CIRC MUD 60 SXS @ 620
			0		✓		200	START DISP
	1615		8		✓		200	PULL 5 1/2" TO 240 FT
	1700	3.0	0		✓		50	START CMT
	1705		5		✓		100	" CIRC MUD 50 SXS @ 240
	1705		14		✓		100	CIRC CMT
								RECEIVED PULL OUT MAR 12 2009 KCC WICHITA
	1730		5.0		✓			TOP OFF 8 5/8
	1750		5.5		✓			STANDING FULL! 20 SXS
	1830							JOB COMPLETE  THANK YOU! DAVE JOSH B SCOTT