

15-195-00256-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County. Sec. 1 Twp. 11 Rge. 23 (E7) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SW

Lease Owner Veeder Supply & Development Co. et al

Lease Name Howat Well No. 1

Office Address P. O. Box 201, Cherryvale, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 19 19 54

Application for plugging filed March 19 19 54

Application for plugging approved March 19 19 54

Plugging commenced March 19 19 54

Plugging completed March 19 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4040 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated heavy mud 4040' to 260', plug at 260'; 1/2 sack hulls on plug, 15 sacks cement 260 to 215'; mud 215 to 40'; plug at 40' 1/2 sack hulls on plug; 10 sacks cement 40' to 7' below ground surface

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply & Development Co.

Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.

Floyd W. Hild (employee of owner) or ~~owner or operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd W. Hild

Cherryvale, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 54

Cleo Lawson

Notary Public.

My commission expires July 11, 1956

PLUGGING
FILE 15-195-00256-00-00
BOOK PAGE 22 LINE 13

15-195-00256-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas Co.- Herman Kaiser Farm Howat No. 1 Depth 4040'
 Contractor Veeder Supply & Development Co. Pipe 275' 8 5/8" csg. cemented w/160 sks. cement
 Location NW NW SW Sec. 1 Twp. 11 Range 23W
 Commenced 3-8-54 Completed 3-19-54 County Trego State Kansas

	0	39	39	Tops:	
Soil	0	39	39		
Sand	39	45	6		
Sand and shale	45	250	205	Heebner	3507
Blue shale	250	270	20	Toronto	3526
Shale	270	400	130	Lansing	3543
Shale, shells	400	800	400	Arbuckle	3986
Sand phrety	800	940	140		
Sand, shale, phrety	940	975	35		
Sand, shale	975	1500	525		
Shale, red bed	1500	1768	268		
Anhydrite	1768	1810	42		
Shale and shells	1810	2125	315		
Lime and shale	2125	3472	1347		
Lime	3472	3800	328		
Lime and shale	3800	3855	55		
Lime, shale, cert	3855	3888	33		
Lime and shale	3888	3930	42		
Cherty Conglomerate	3930	3986	56		
Lime	3986	4040	54		
Total Depth	4040				

Dry and Plugged

AFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath, deposes and says:

That I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state that the above drilling log covering the Howat #1 in Section 1-11-23W, Trego County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Floyd W. Hild
Floyd W. Hild

Subscribed and sworn to before me this 23rd day of March, 1954.

Leo Lawson
Notary Public

My commission expires July 11, 1956.

PLUGGING
TWP. SEC. 11 R. 23W
BOOK PAGE 22 LINE 23

3-31-1954

COMMISSIONER OF MINES
STATE OF KANSAS