


15-195-00308-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 1 Twp. 11 Rge. (E) 23 (W)
Location as "NE/CNW%SW%" or footage from lines SE NE NE
Lease Owner Petroleum, Inc.
Lease Name HOWAT 'C' Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 7, 19 55
Application for plugging filed May 7, 19 55
Application for plugging approved May 7, 19 55
Plugging commenced May 7, 19 55
Plugging completed May 7, 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. H. Horner
Producing formation Depth to top Bottom Total Depth of Well 4060 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud up with heavy mud to 220', pushed down

1/3 sack hulls to 220' followed by wooden plug. Placed

20 sacks cement through drill pipe onto plug. Mud up

to 35' and place 1/3 sack hulls at 35' followed by

wooden plug and 10 sacks cement to base of well cellar.

RECEIVED
STATE CORPORATION COMMISSION
5-19-1955
MAY 19 1955

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Karl E. Becker (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E Becker

311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of May, 19 55

My commission expires

8-11-58

Notary Public.

PLUGGING
FILE SEC 1 T 11 R 23
BOOK PAGE 117 LINE 17

WELL LOG

15-195-00308-00-00

COMPANY **Petroleum, Inc.**

SEC. 1 T. 11 R. 23W

FARM **HOWAT 'C'**

NO. **1**

LOC. **SE NE NE**


TOTAL DEPTH **4060'**

COUNTY **Trego County, Kansas**

COMM. **April 26, 1955**

COMP. **May 7, 1955.**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 222' w/150 sax.**

ELEVATION **2269' DF
2271' RB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Clay & Sand
180	Shale & Sand
222	Rock & Shale
620	Shale
1080	Sand, Shale & Shells
1115	Anhydrite
1350	Shale & Shells
1525	Sand
1680	Shale & Shells
1763	Shale & Red Bed
1800	Anhydrite
2350	Shale & Shells
3500	Lime & Shale
3540	Lime
3600	Lime & Shale
3655	Lime
3705	Lime & Shale
3785	Lime
3870	Lime & Shale
3906	Shale, Lime & Chert
4018	Lime & Shale
4037	Chert
4060	Lime
R.T.D.	4060

Tops:

Heebner:	3513	(-1242)
Toronto:	3434	(-1263)
Lansing:	3550	(-1279)
Arbuckle:	4026	(-1755)

State of **KANSAS**

County of **SEDGWICK**

ss:

PLUGGING
 FILE SEC. 1 T. 11 R. 23W
 BOOK PAGE 17 LINE 17

RECEIVED
 STATE CORPORATION COMMISSION
 5/19/1955
 MAY 19 1955
 CONSERVATION DIVISION
 Wichita, Kansas

I, **Karl E. Becker** of **Petroleum, Inc.**

upon oath state that the above and foregoing is a true and correct copy of the log of the **HOWAT 'C' #1** well

Subscribed and sworn to before me this **16th** day of **May**, 19 **55**

My Commission Expires: **8-11-58**



Karl E. Becker

[Signature]
NOTARY PUBLIC