

15-195-30104-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

10-6-1965

OCT 6 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Nadel and Gussman,

Complete Address: 625 Union Center, Wichita, Kansas.

Lease Name Akers Well No. 1

Location N/2-N/2-NW/4 Sec. 9 Twp. 11 Rge. (E) (W) 21

County Trego Total Depth 3800

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: D & D Drilling Company, Incorporated,

Address: 307 Schweiter Building, Wichita, Kansas. License No.

Operation Completed: Hour 11:00AM Day 1 Month 10 Year 1965

The Above well was plugged as follows:

229'--8 5/8" Surface pipe, cement circulated with 190 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug and displaced 20 Sx. cement

thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement

to bottom of cellar.

(Cement operations performed by Sun Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 10/6/65  
INV. NO. 1928-W