

15-195-20052-00-00

Form CP-3
Rev. 6-9-67

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-6-1967
DEC 6 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Lee Phillips Oil Company and Braden Drilling, Incorporated.,

Complete Address 1532 Wichita Plaza, Wichita, Kansas,

Lease Name Taylor Well No. 1

Location SW-NW-NW Sec. 10 Twp. 11 Rge. (E) (W) 21

County Trego Total Depth 3735'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Braden Drilling, Incorporated,

Address 1620 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 9:30AM Day 28 Month 11 Year 1967

The above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 600' to 800'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement from
800' to 480'. Pulled DP to 240' and displaced 25 Sx. cement from 240' to 165'.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Pichele*
Well Plugging Supervisor

INVOICED
DATE 12/6/67
INV. NO. 6849-W