

15-195-00280-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE NW NE

SEC. 10 TWP. 11 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Waltz ~~Waltz~~

Operator I. O. Miller Address Wichita, Kans 619 Brown Bldg

Field _____ County Trego

Total Depth 3760 Feet.

Plugging Contractor Virginia Drg Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 600', displaced 25 sax cement through drill pipe at 600', heavy mud to 240', set cementing plug and displaced 15 sax cement through drill pipe at 240', heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

District Conservation Agent

Date 7-22-57

PLUGGING
FILE SEC. 10 T. 11 R. 21w
BOOK PAGE 31 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
7-26-1957
JUL 26 1957
CONSERVATION DIVISION
Wichita, Kansas