

15-195-00246-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 138-15

LOCATION SE NW NW

SEC. 24 TWP. 11 RGE. 21

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. A-1 Lease Nicholson

Operator Stanolind Oil & Gas Address Box 1654 Oklahoma City

Field \_\_\_\_\_ County Trego

Total Depth 3814 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 220' circulated with cement - 5 1/2" at 3801' with 200  
sax cement behind - perforated at 3790'.

Filled with sand to 3780', set 4 sax cement with dump bailer,  
pulled 2045' 5 1/2" - filled with mud to 220', set rock and 15 sax  
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
8-12-1955  
AUG 12 1955

District Conservation Agent

Date 8-10-55

PLUGGING  
FILE SEC 24 TWP. 11 RGE. 21  
PAGE 138 LINE 15

CONSERVATION DIVISION  
Wichita, Kansas