

15-195-20904-00-00

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-195-20,904-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Voyager Petroleum Inc.

Complete Address Petroleum Bldg Suite 800, 110 Fifteenth, Denver, Colo 80202

Lease Name Schubert Well No. 31-4

Location NW-NW Sec. 31 Twp. 11 Rge. 21 (East) (West)

County Neogo Total Depth 4160

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hambree Well Service Rig # 16

Address Ness City, Kansas License No. 960

Operation Completed: Hour: 5:50 Day: 14 Month: Jan Year: 19 82

Plugging Operations attended by Agent?: All X Part None

The above well was plugged as follows: Slw - 2360 Sun

8 5/8" - 259' S.P. circ w/ 190 SK Comm. Cmt. -> 4 1/2" set @ 4160' w/ 240 SK Cmt

Plug back 3574' -> 50' sand + 5 SK cmt. : Perfs at 3726'

Shot Casing @ 3230 -> Recovered 3230'

Ordered 140 SK 50% proppant 4% gel - 32 Cmt. -> 23 gel -> 5 hulls -> 8 5/8" plug

Pumped in w/ pump truck 4 hulls -> 15 SK gel -> 70 SK cmt ->

8 gel -> Rel. Plug -> 70 cmt.

May P.S.I 400# Commented by Sun

Amount of Surface Casing: 259' S.P. 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1982
1-19-1982

Signed: _____
Conservation Division Agent

2-9-82
9379-W