

15-195-00437-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-13-1962
NOV 1 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Glickman Oil Co
Complete Address: 702 S St Francis Wichita, Kansas
Lease Name Cockrell Well No. 1
Location NW NE NW Sec. 35 Twp. 11 Rge. (E) (W) 21
County Trego Total Depth 3971
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons
Address: Russell, Kans License No. 9
Operation Completed: Hour 10AM Day 10 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 203' circulated with cement. 5 1/2" 3970' with 75 sax cement -
perf 3910'

Filled with sand to 3890', set 5 sax cement with dump baller - pulled
3365' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (32 sax
Gel mud) - displaced 20 sax cement through 5 1/2" at 550', heavy mud to
180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35' -
cement 35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/13/62
INV. NO. [Signature] 6010-W