

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20327-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

525-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name James J. Simmons- National Oil Company,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Riffel Well No. 1

Location SE-SE-NW Sec. 27 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 8:45 AM Day 21 Month 5 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/25/70

INV. NO. 1931-W