

15-065-20325-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1970

CONSERVATION DIVISION
Wichita, Kansas

5-19-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Oil Company,

Complete Address 200 W. Douglas
Suite 550, O. W. Garvey Building, Wichita, Kansas.

Lease Name Law Well No. 1

Location NW-NW-SE Sec. 27 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 7:00 AM Day 12 Month 5 Year 1970

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud, pulled Dp to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 5/22/70
INV. NO. 1918-W