

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12-6-1968  
DEC 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Prospect Oil and Shields Drlg.

Complete Address: 811 Union Center Wichita, Kansas

Lease Name Bowlby Well No. 1

Location NE NE SE Sec. 23 Twp. 11 Rge. 16 (E) (W) X

County Ellis Total Depth 3061

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Shields Drlg.

Address:      License No.     

Operation Completed: Hour 7:30P Day 4 Month 12 Year 1968

The Above well was plugged as follows:

RTD 3061 8 5/8 csg set at 254' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sc cmt.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/6/68  
INV. NO. 8959-W

Signed: Leo F. Massey  
Well Plugging Supervisor