

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,441-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name C. B. and J. B. Oil Company

Complete Address R. R. #1, Natoma, Kansas 67650

Lease Name Chrisler "B" Well No. #1

Location NW SW NW Sec. 25 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3441'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereinafter indicated     

Plugging Contractor Emphasis Oil Operations

Address Box 506, Russell, Kansas 67665 License No.     

Operation Completed: Hour: 3:30 PM Day: 28th Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part      None     

The above well was plugged as follows:

8 5/8"-907' s.p. cuc. w/350 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 310' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 907' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

    

    

    

    

    

RECEIVED  
STATE CORPORATION COMMISSION  
2-2-1982  
FEB - 2 1982  
Conservation Division Agent  
CONSERVATION DIVISION  
Wichita, Kansas

23-82  
9183-W