


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 11 Twp. 11 Rge. 19 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Okmar Oil Company  
Lease Name Gasaway Well No. #2  
Office Address 405 Schweiter Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed March 1 19 53  
Application for plugging filed March 1 19 53  
Application for plugging approved March 1 19 53  
Plugging commenced March 1 19 53  
Plugging completed March 1 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	138'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed bottom plug to 130', set with 1/2 sacks hulls and 15 sacks cement, filled to 140', set top plug at 140' with 10 sacks cement, cemented to bottom of cellar.

RECEIVED  
3-25-1953  
DIVISION


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn R. Nye Drilling Company  
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye  
\_\_\_\_\_  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of March, 19 53  
My commission expires May 9, 1953  
John L. Spress Notary Public.



24-2675-S 2-52-20M

PLUGGING  
FILE SEC 11 T 11 R 19 W  
BOOK PAGE 22 LINE 17

15-051-00193-00-00

Company: Okmar Oil Company  
Contractor: Glenn R. Nye Drilling Company  
Commenced: February 16, 1953  
Completed: March 1, 1953

Location: NE SE NW Sec. 11-11-19  
Ellis County, Kansas  
Farm: Gasaway #2  
Casing Record: 8 5/8" set at 138'  
Elevation: 2054 D.F.

(figures below indicate bottoms)

Post rock & sand	55	
blue shale	70	
surface shale & gumbo	138	
gumbo & shale	250	
shale	320	
sand & shale	490	
sand & gumbo	630	
sand	770	
shale & lime	880	
shale & sand	1012	
shale & red bed	1375	
anhydrite	1415	
red bed & shale	1600	
shale & red bed	1940	
red bed & shale	1960	
shale & lime streaks	2077	
lime & shale	2155	
shale & lime	2305	
lime & shale	2355	
lime & shale	2450	
lime & shale	2600	
lime & shale	2670	
lime & shale	2730	
lime & shale	2845	
lime & shale	2985	
lime & shale	3045	Topeka 3014'
lime	3048	D.S.T. 3048
lime & shale	3120	
lime & shale	3180	
lime & shale	3202	
lime	3240	Heebner 3236'
lime & shale	3285	
lime & shale	3305	
lime	3346	
lime	3386	
lime	3417	D.S.T.
lime	3438	
lime	3453	
lime	3498	
cherty lime	3540	Conglomerate 3512'
lime & shale	3577	
simpson	3588	
simpson	3593	
arbuckle	3597	
arbuckle	3607	
lime arbuckle	3645	T.D. 3645'

3-25-1953

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

PLUGGING  
FILE SEC 11-11-R-19  
BOOK PAGE 22-17

GLENN R. NYE DRILLING COMPANY  
*Glenn R. Nye*

STATE OF KANSAS  
ELLIS COUNTY

Subscribed to and sworn to before me, a notary public, in and for said County and State this 16th day of March, 1953.

*John L. Spiess*  
Notary Public

My Commission Expires May 9, 1953