


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 8 Twp. 11 Rge. 19 (E) W (W)
Location as "NE/CNW/SW" or footage from lines ne ne se
Lease Owner Okmar Oil Company
Lease Name Gintner Well No. 1
Office Address 817 Union National Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 30 19 54
Application for plugging filed May 30 19 54
Application for plugging approved May 30 19 54
Plugging commenced 12 a.m. May 30 19 54
Plugging completed May 30 19 54
Reason for abandonment of well or producing formation Too low structurally.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	171.45'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 166'. Set plug, Put in 1/2 sack Hulls & 20 sacks cement. Filled hole with mud to 40'. Set plug then filled to top with 10 sacks cement and 1/2 sack Hulls.

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 - 1954
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Bldg., 321 E. William, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. A. COOK (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R A Cook
107 Rule Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of June, 19 54

My commission expires June 25, 1955



Wick Fritz
Notary Public.

PLUGGING
FILE SEC. 8 TWP. 11 R 19W
BOOK PAGE 32 LINE 45

15-051-00472-00-00

-: CONTRACTOR'S WELL LOG :-

OPERATOR Okmar Oil Company FARM NAME Giinther Well #1
 LOCATION NE NE SE Sec. 8-11-19W
 POOL NAME _____ COUNTY Ellis STATE Kansas
 COMMENCEMENT DATE May 21, 1954 COMPLETION DATE May 30, 1954

LOG OF WELL

Elevation: 2053 RB
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	171	Shale-Sand		
171	800	Sand-Shale		
800	1070	Sand		
1070	1401	Red Bed		
1401	1438	Anhydrite		
1438	1910	Shale-Shells	0° - 1500'	
1910	2155	Line-Shale	0° - 2000'	
2155	2330	Line-Shale		
2330	2465	Line-Shale		
2465	2660	Line-Shale	0° - 2500'	
2660	2745	Line-Shale		
2745	2930	Shale-Lime		
2930	3055	Line-Shale	0° - 3000'	
3055	3145	Line-Shale		
3145	3190	Line-Shale		
3190	3250	Line-Shale		
3250	3297	Line-Shale		
3297	3355	Line-Shale		
3355	3389	Line-Shale		
3389	3434	Line-Shale		
3434	3467	Line-Shale		DST 3444'-3467'
3467	3485	Line-Shale		
3485	3540	Line-Shale	0° - 3500'	
3540	3590	Line-Shale		
3590	3614	Line-Shale		
3614	3653	Line		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 171.45' 8-5/8" OD Surface Casing.

RECEIVED
 STATE CORPORATION COMMISSION
 6-3-1954
 JUN 3 - 1954

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By R.G. Cook
 Partner

Subscribed and sworn to before me this 1st day of June, 1954.

My commission expires June 25, 1955.

Vicky Lutz
 Notary Public



PLUGGING
 NE SEC 8-11-19W
 BOX PAGE 32 LINE 45