



15-051-01199-00-00

OKMAR OIL CO.  
Marietta, Ohio

COMPANY: H. APPLEMAN Co.  
New York, N. Y.

Rotary Drilling Commenced: 5-24-50  
Rotary Drilling Completed: 6-2-50

LOCATION: CASAWAY #1  
NE NE 1/4, Sec. 11-118-197  
Ellis County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY, INC.  
Wichita, Kansas

CASINO RECORD: 157' (5 Jts.) Log 3 5/8" 24' seamless casing set at 157' in  
a 12 1/4" hole, cemented with 75 sacks cement  
3672' (112 Jts.) Log 5 1/2" 14' seamless casing set at 3672'  
in a 7 7/8" hole, cemented with 150 sacks cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Collar	8	Circulate for samples at 3133'
Post Rock	45	Circulate for samples at 3170'
Shale	157	Circulate for samples at 3190'
Shale & Shells	500	Circulate for samples at 3419'
Sand	740	Circulate for samples at 3546'
Shale & Shells	910	Circulate for samples at 3656'
Sand	1175	Circulate for samples at 3659'
Shale & Shells	1440	Circulate for samples at 3664'
Anhydrite	1475	Circulate for samples at 3668'
Shale & Shells	1650	Circulate for samples at 3672'
Shale & Lims	2200	Circulate for samples at 3678'
Lims & Shale	2375	
Iron	2395	Slope test at 500' - 0° off.
Lims & Shale	2972	SLM at 500' - O. K.
Lims	3665'	Slope test at 1000' - 0° off.
		SLM at 1000' - O. K.
		Slope test at 1500' - 0° off.
		SLM at 1500' - O. K.
		Slope test at 2000' - 0° off.
		SLM at 2000' - O. K.
		Slope test at 2500' - 0° off.
		SLM at 2500' - O. K.
		Slope test at 3000' - 0° off.
		SLM at 3000' - O. K.
		Slope test at 3500' - 0° off.
		SLM at 3500' - O. K.
		Slope test at 3665' - 0° off.
		SLM at 3665' - O. K.

GEOLOGICAL DATA:

Topoka: 3068  
Hobbs: 3291  
Lansing: 3332  
Conglomerate: 3570  
Arbuckle: 3648

Lost Circulation at 3550'

THE undersigned, C. W. Sobitz, Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

RECEIVED PICKRELL DRILLING COMPANY, INC.

Conservation Div. By C. W. Sobitz  
Secretary

8-24-1950  
AUG 24 1950

PLUGGING

STATE CORPORATION  
COMMISSION FILE SEC 11-T-11-R-196  
KANSAS PAGE 23 LINE 29



BE IT REMEMBERED that on this 18th day of June, 1950, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came C. W. Sobitz, Secretary of Pickrell Drilling Company, Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My commission expires January 6, 1954.

Dorothy MacConley