

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County. Sec. 11 Twp. 11 Rge. 19 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner Okmar Oil Company

Lease Name Vine Well No. 1

Office Address 405 Schweiter Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed April 22 19 53

Application for plugging filed April 22 19 53

Application for plugging approved April 22 19 53

Plugging commenced April 22 19 53

Plugging completed April 22 19 53

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3588 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	156'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Double plug set at 150' with 1/2 sack hulls and cemented through drill pipe with 50 sacks cement by Sun Oil Well Cementing Company.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing Company

Address Hays, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.

Claude N. Bard (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Claude N. Bard

Hays, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1953

My commission expires May 9, 1953

24-2875-S 2-52-20M

PLUGGING
FILE SEC 11 T 11
BOOK PAGE 96 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
5-6-1953
MAY - 6 1953
CONSERVATION DIVISION
Wichita, Kansas

15-051-00234-00-00

Company: Okmar Oil Company
Contractor: Glenn R. Nye Drilling Company
Commenced: April 10, 1953
Completed: April 22, 1953

Farm: Vine #1
Location: SW SW SE Sec. 11-11-19,
Ellis County, Kansas
Casing Record: 8 5/8" set at 156'
Dry and Abandoned
Elevation: 2003 D.F.

(figures below indicate bottoms)

surface soil & clay	20	
gravel & sand	85	
sand & shale	120	
blue shale	160	
shale	360	
shale & sand	524	
sand	645	
shale & sand	780	
sand & shale	850	
sand & shale	1000	
red bed & shale	1348	
red bed & shale	1365	
anhydrite	1395	
red bed & shale	1650	
salt-shale & shell	1700	
shale & shells	1880	
shale & lime streaks	1945	
lime & shale	2105	
lime & shale	2240	
lime & shale	2330	
shale & lime	2445	
shale & lime	2520	
lime & shale	2630	
shale	2785	
shale & lime	2865	
shale & lime	2985	Topeka 2992'
lime & shale	3050	
lime & shale	3117	
lime & shale	3150	
lime	3195	
lime	3240	Heebner 3217'
lime	3280	K.C. 3258'
lime & shale	3325	Elevation 2003' D.F.
lime & shale	3365	
lime	3405	
lime	3437	
lime	3480	
conglomerate	3538	Conglomerate 3496'
simpson shale	3560	Simpson 3540'
lime	3573	Arbuckle 3567'
arbuckle	3578	
T. D.	3588	

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Claude N. Bard

RECEIVED
STATE CORPORATION COMMISSION
5-6-1953
MAY - 6 1953

STATE OF KANSAS)
) SS
ELLIS COUNTY)

CONSERVATION DIVISION

Subscribed to and sworn to before me, a notary public, in and for said County and State this 2nd day of May, 1953.

John L. Shiss
Notary Public

My Commission Expires May 9, 1953

PLUGGING
FILE SEC-11-T-11-R-194
BOOK PAGE 96 LINE 28