


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 1 Twp. 11 Rge. 19 X/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____
SE SE SE

Lease Owner J. B. Collins
Lease Name Peavy Well No. 21 CS
Office Address 1007 Cody Ave. Suite A, Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 3-28 19 81
Application for plugging filed 3-28 19 81
Application for plugging approved 3-28 19 81
Plugging commenced 3-28 19 81
Plugging completed 3-29 19 81
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	171'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 720' with 65 sacks cement
2nd plug @ 180' with 30 sacks cement
3rd plug @ 40' with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc., Victoria, KS 67671


STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Patty Dreiling, of Dreiling Oil, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Patty Dreiling
Patty Dreiling, Victoria, KS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 81

My commission expires 1-19-85

Cecilia Basgall
Cecilia Basgall STATE OF KANSAS Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

15-051-22345-00-00

WELL LOG

Company	J. B. Collins 1007 Cody Ave. Suite A Hays, KS 67601	Sec. 1	Twp. 11	Rng. 19W
Farm	Peavy No. <i>2 1 53 11a 109</i>	Location	SE SE SE	
Total Depth	3650'	County	Ellis	
Comm.	3-21-81	Comp.	3-28-81	Elevation: 2063' K. B.
Contractor	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671		2060'	D. F.
			2058'	G. R.

Casing Record

Cement Record

Production:

171- 8 5/8"

130 sacks cement

D & A

Figures Indicate Bottom of Formations

0'	174'	Shale
174'	499'	Shale
499'	860'	Shale
860'	1087'	Sand
1087'	1230'	Shale
1230'	1397'	Shale
1397'	1435'	Anhy.
4135'	1884'	Shale
1884'	2128'	Shale & Lime
2128'	2379'	Lime & Shale
2379'	2637'	Lime & Shale
2637'	2775'	Shale & Lime
2775'	2986'	Lime & Shale
2986'	3148'	Lime & Shale
3148'	3277'	Lime
3277'	3360'	Lime
3360'	3378'	Lime
3378'	3400'	Lime
3400'	3483'	Lime
3483'	3510'	Lime
3510'	3550'	Lime
3550'	3650'	Lime
3650'	T.D.	

STATE CORPORATION COMMISSION
4-7-1981
APR 7 1981

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Patty Dreiling, of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Peavy #2.

Patty Dreiling
Patty Dreiling

Subscribed and sworn to before me this 6th day of April, 1981.

Cecilia Basgall
Cecilia Basgall Notary Public

My commission expires: 1-19-85

