

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,214-0000

LEASE NAME Shaw

WELL NUMBER #1

SPOT LOCATION 130' N NW NW

SEC. 7 TWP. 9S RGE. 28 (W)

COUNTY Sheridan

Date Well Completed 6-3-69

Plugging Commenced 3-26-85

Plugging Completed 3-26-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 905 Century Plaza, Wichita, Ks. 67202

PHONE (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? NA If not, is well log attached? copies of well log & data & affid

Producing formation Toronto & Lans Depth to top _____ bottom T.D. 4079'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface 8	5/8" 210' set	@ 210'	w/160	s.x.		
Production 4	1/2" 4088.27'	set @ 4078'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged w/4 sx. hulls w/10 sx. gel added, 50 sx. 50-50 posmix, 6% gel, 3% c.c. 12 sx. gel, 10 sx. cement. Pressure in @ 3000#, started @ 9:00 a.m. Comp. @ 10:20 p.m.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chief Drilling Co., Inc. License No. 5886
Address 905 Century Plaza, Wichita, Ks. 67202

RECEIVED


STATE OF Kansas COUNTY OF Sedgwick, ss.

STATE CORPORATION COMMISSION

4-15-85
APR 15 1985

F.W. Shelton, Jr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas



(Signature) F.W. Shelton, Jr.
(Address) 905 Century Plaza
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 85

My Commission expires: Martha E. Gustin

Notary Public
Martha E. Gustin

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

SHAW #1
130' N NW NW Sec. 7-9S-28W
Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 6-12-69
Completed: 6-21-69

Casing Record: 210' 8 5/8" w/160 sacks.
4088.27' of 4 1/2" set @4078' w/200 sacks 60/40 Pozmix
DV Tool cemented w/600 sacks 50-50 Pozmix @2350.

FORMATION	FROM	TO	ELEVATION
			2706 Gr.
			2708 D.F.
			2711 K.B.
Sand	0	40	
Shale & sand	40	1817	
Shale & shell	1817	1890	
Shale, Shell, & sand	1890	2132	
Red Bed & Shale	2132	2323	
Anhydrite	2323	2360	
Shale & shells	2360	2575	
Shale & lime	2575	3830	
Lime	3830	4035	
Lime & shale	4035	4080	
Total depth	4080		

FORMATION TOPS	
Anhydrite	2323 + 388
Heebner	3782 -1071
Toronto	3802 -1091
Lansing	3817 -1106
RTD	4080 -1369

STATE OF KANSAS, COUNTY OF BARTON) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled 130' N NW NW of Section 7-9S-28W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 28th day of June, 1969.

My Commission Expires: March 25, 1972

Clydene Williams
Clydene Williams
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1985

CONSERVATION DIVISION
Wichita, Kansas

