

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-179-20,568-0000

LEASE NAME Mosier

WELL NUMBER #6-32

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 6 TWP. 9 SRGE. 28 (E) or (W)

COUNTY Sheridan

Date Well Completed 10-18-80

Plugging Commenced 11-4-85

Plugging Completed 11-5-85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Oxford Exploration Company

ADDRESS 1801 California St. #200 Denver, CO 80202

PHONE# (303) 292-3111 OPERATORS LICENSE NO. 6889

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow, Hays, Kansas

is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation Lansing Depth to Top 3846 Bottom 4081 T.D. 4130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	3874	3877	4 1/2"	4005'	1279'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

11/4/85 Moved in, rigged up. Sand to 3500'.

11/5/85 Dumped 4 sx cement on top of sand with dump bailer. Shot off at 1279'. Cemented with Halliburton 3 sx hulls, 20 sx gel, 100 sx cement 60/40, 3% cc, 1 sx hulls, 20 sx gel, 80 sx cement 60/40, 3%cc. 300# pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Well Service License No. \_\_\_\_\_

Address Box 115 Oberlin, Kansas 67749

STATE OF Colorado COUNTY OF Denver, ss.

David E. Park, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David E. Park

(Address) 1801 California St. #200 Denver 80202

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of November, 19 85

Joni S. Kasper  
 Notary Public

STATE CORPORATION COMMISSION

11-25-85  
 NOV 25 1985

My Commission Expires: 4-19-88

Form CP-4  
 Revised 08-84

CONSERVATION DIVISION

