

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,332-0000

LEASE NAME Haffner

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 19 TWP. 9 RGE. 27 (E) or (W)

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS Suite 505 Fourth Financial Ctr., Wichita, Ks.

COUNTY Sheridan

PHONE#(316) 265-6697 OPERATORS LICENSE NO. 5141

Date Well Completed 11-8-72

Character of Well SWDW

Plugging Commenced 6-20-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-20-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #6, Mr. Carl Goodrow, State Plugger

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To	Size	Put in	Pulled out
			246	8 5/8	246	None
	Production		4150	5 1/2	4150	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped in 100 sacks cement, 2 sacks hulls, 10 sacks gel with 1 sack hulls. Pumped in 100 sacks cement with 1 sack hulls. Had returns on 8 5/8" casing. Pumped 100 sacks cement down back side, reached 200# pressure. Pumped in another 100 sacks cement & 10 sacks gel down casing. Plugging completed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Zenith Drilling Corporation License No. 5141

Address Suite 505 Fourth Financial Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK STATE CORPORATION COMMISSION

Sherrill Compton (Employee of Operator or Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Sherrill Compton

(Address) Sherrill Compton, Vice Pres. 505 4th financial Ctr., Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 85

Sharon R. Allen  
Sharon R. Allen Notary Public

My Commission Expires: Dec 15, 1988

RECEIVED  
STATE CORPORATION COMMISSION  
6-26-85  
JUN 26 1985  
CONSERVATION DIVISION  
Wichita, Kansas

