

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,322-0000

LEASE NAME Ochs

WELL NUMBER #1

SPOT LOCATION SE NE

SEC. 24 TWP. 9 RGE. 28W (E) or (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 2-19-86

Plugging Completed 3-5-86

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS 505 Fourth Financial Ctr. Wichita, Ks. 67202

PHONE # (316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4140'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	255'	none
				5-1/2"	4140'	1221'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3800' and 5 sacks cement. Shot casing @2500', 2000', 1800', 1624', 1423', 1221', pulled a total of 38 joints of 5-1/2" casing (1221').
Plugged surface with 3 hulls, 20 gel, 100 cement w/1 hull, 20 gel, 80 cement, 60/40 pos, 3% cc. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso


MAK 10 1986
3-10-86

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1986
Wichita, Kansas

Irene Hoover
Notary Public

My Commission expires:



Don R Pate

15-174-20322-0000

GEOLOGICAL AND GEOPHYSICAL CONSULTANT

UNION CENTER BLDG.

WICHITA, KANSAS

AM2-5993

GEOLOGIST'S REPORT

DRILLING TIME AND SAMPLE LOG

COMPANY Zenith Drilling Corp., INC.

LEASE Ochs

FIELD Wildcat

LOCATION SE - NE

SEC. 24 TWSP. 9S RNG. 28W

COUNTY Sheridan STATE Kansas

ELEVATIONS

K.B. 2754

D.F. 2752

G.L. 2746

Measurements Are All
From 2754

CONTRACTOR Abercrombie Drlg.

COMM. 8 - 21 - 72 COMP. 8 - 29 - 72

RTD 4140 LTD 4142

MUD UP _____ TYPE MUD Chem.

BASING
SURFACE 8 @ 255'
PRODUCTION 5 1/2 @ 4120

ELECTRICAL SURVEYS
Electra
Radiation-Accurlog

SAMPLES SAVED FROM 3500 TO 4140

DRILLING TIME KEPT FROM 3500 TO 4140

SAMPLES EXAMINED FROM 3500 TO 4140

GEOLOGICAL SUPERVISION FROM 3750 TO 4140

GEOLOGIST ON WELL Don R. Pate

FORMATION TOPS

Anhydrite

Heebner

Lansing

Base of K.C.

Total Depth

Sample

Elec. Log

2359	(+359)	2359	(+359)
3851	(-1097)	3853	(-1099)
3882	(-1128)	3882	(-1128)
4132	(-1368)	4134	(-1370)
4140	(-1376)	4142	(-1378)

STATE CORPORATION COMMISSION

JAN 21 1986

CONSERVATION DIVISION




EXHIBIT "C"