

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-179-20,694-0000

LEASE NAME Mosier 'B'

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP. 9S RGE. 27 (E) or (W)

COUNTY Sheridan

Date Well Completed 9/6/83

Plugging Commenced 12/29/94

Plugging Completed 12/29/94

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P.O. Box 70 Hays KS 67601

PHONE# (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/27/94 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing-Kansas City Depth to Top 3794' Bottom 4021' T.D. 4065'

PBTD 4022'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		245'	0	8 5/8"	245'	0
		4056'	0	5 1/2"	4056'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate Anhydrite (2250)' and base of Dakota (1400)'. Pump down 8 5/8"-5 1/2" annulus 50sx 60/40 poz 10% gel with 100# hulls, shut in pressure 150 psi. Pump down 5 1/2" casing 50sx 60/40 poz 10% gel with 300# hull, followed by 13 sx gel, followed by 175 sx 60/40 poz 10% gel with 200# hull, max pressure 500 psi, shut in pressure 150 psi. Plug job complete. Witnessed by Carl Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License 1-9-95

Address P.O. Box 31 Russell KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____



AND SWORN TO before me this 3rd day of January, 19 95

Kimberly J. Maddy
 Notary Public

My Commission Expires: 2-3-98

