

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-179-20347-0001

API NUMBER 11-17-73

LEASE NAME McFADDEN

WELL NUMBER #1

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 9S RGE. 27X or (W)

COUNTY Sheridan

Date Well Completed 1-10-74

Plugging Commenced 6-20-91

Plugging Completed 6-20-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

ADDRESS 220 West Douglas, Suite 435, Wichita, KS 67202

PHONE# (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well Oil SWD
^{RTKCC}
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 17th, 1991 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top _____ Bottom _____ T.D. 4083

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

ION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	3959'	3995'	4 1/2"	4078'	None

7-22-91
 2-2-1991

REGISTRATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Squeezed 4 1/2" with 243 sx. cement blend to max. PSI 300#.
Closed in pressure at 150#.
Squeezed 8 5/8" with 80 sx. cement blend to max. PSI 300#.
Closed in pressure at 150#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 683

Address 220 West Douglas, Suite 435, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rains & Williamson Oil Co., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Wilson Rains, President of Rains & Williamson Oil Co., Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wilson Rains

(Address) 220 W. Douglas, Suite 435, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 91



Teresa L. Burleigh-Smith
 Notary Public
 My Commission Expires: 7-2-94

15-179-20347-0001

WELL LOG

RAINS & WILLIAMSON
435 Page Court
Wichita, Kansas 67202

#1 McFADDEN-WASH DOWN
SE NE NE Sec. 9-9-27W
Sheridan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 8 5/8" at 286'
Set 4 1/2" at 4078' w/150 sacks
60-40 Posmix

COMMENCED: 11/5/73
COMPLETED: 11/16/73

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Old well wash down	0	1300	2672 Gr.
Shale & Sand	1300	1725	2674 D.F.
Shale	1725	1840	2675 K.B.
Shale & Sand	1840	2235	
Shale & Lime	2235	2266	
Anhydrite	2266	2300	
Shale & Lime	2300	2785	
Lime, Shale & Sand	2785	2950	
Lime & Shale	2950	3375	
Lime	3375	4080	
Total Depth	4080		

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1974
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NE NE of Section 9-9-27W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn to before me this 20th day of November, 1973

Virginia S. Fabian
Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:

August 5, 1975
NOTARY
PUBLIC
SEDGWICK CO., KANS.