

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,585-0000

LEASE NAME Mosier 'A'

WELL NUMBER #1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 3 TWP. 9 RGE. 27 (E) or (W)

COUNTY Sheridan

Date Well Completed 3/18/81

Plugging Commenced 5/19/92

Plugging Completed 5/19/92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Skyline Petroleum

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE# (913) 625-0020 OPERATORS LICENSE NO. 6066

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/19/92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? yes

Producing Formation Lansing-Kansas City Depth to Top 3739 Bottom 3917 T.D. 3992

PBTD 3898

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		239	surf.	8 5/8	239	0
		3954	surf.	5 1/2	3954	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate base of Dakota (1480') and Anhydrite (2220'). Pump 75 sx 60/40 pozmix cement w/10% gel, 1/4 lb floseal and 100# hulls down 8 5/8-5 1/2" annulus, max pressure 100#, shut in pressure 100#. Pump 325 sx 60/40 pozmix cement w/1/4 lb floseal, 10% gel, and 400# hulls down casing, max pressure 150#, shut in pressure 50#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Skyline Petroleum

STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 29th day of May



My Commission Expires: 1-10-95

Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6-1-92  
11-1992

3-9-27W

# BIG SPRINGS DRILLING, INC.

P.O. BOX 8287  
MUNGER STATION  
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

15-179-20585-0000

February 20, 1981

*State Geological Survey*

## DRILLERS LOG

RE: Mosier A - #1  
SW SW NW  
Sec. 3 Twp 9S Rg 27W  
Sheridan County, Kansas

OPERATOR: Arrowhead Petroleum, Inc.  
CONTRACTOR: Big Springs Drilling, Inc.  
COMMENCED: February 2, 1981  
COMPLETED: February 12, 1981

Surface Pipe: 237' w/200 SX Common 2% gel 3% ccl

0	240'	Surface clay & Shale
240'	1050'	Clay & Shale
1050'	1827'	Shale
1827'	1983'	Sand
1983'	2197'	Shale
2197'	2232'	Anhydrite
2232'	3570'	Shale
3570'	3707'	Shale w/lime & Streaks
3707'	3735'	Shale & Lime
3735'	3774'	Lime
3774'	3780'	Lime & Shale
3780'	3964'	Lime
3964'	3990'	Lime & Shale
3990'		RTD


53231291  
FEB 23 1981  
STATE GEOLOGICAL SURVEY  
WICHITA, KANSAS

We certify that the above and foregoing is a true and correct copy of the log on the Mosier A - #1 located in Sheridan County, Kansas.

Big Springs Drilling, Inc.

*Paul A. Seymour, Jr.*  
Paul A. Seymour, Jr.

Subscribed and sworn to before me this 20th day of February, 1981.

  
RUTH M. BASSETT  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Commission Expires \_\_\_\_\_  
My Appt. Exp. \_\_\_\_\_  
1983

*Ruth M. Bassett*  
Ruth M. Bassett Notary Public