

15-179-05605-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Transue

WELL NUMBER #2

SPOT LOCATION SE NW SE

SEC 18 TWP. 9S RGE 26W (E) or (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 3-4-86

Plugging Completed 3-6-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KRM Petroleum Corporation

ADDRESS 1900 Grant St. Suite 300, Denver, Colorado 80203

PHONE # (303) 830-6601 OPERATORS LICENSE NO. 6420

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4042'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	311'	none
				4-1/2"	4041'	1033'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Mud and sand on bottom @3380', ran 4 sacks cement on top of sand. Shot pipe @2827', 2514', 2033', 1498', 1033', pulled a total of 33 joints (1033') of 4-1/2" casing. Plugged surface with 4 hulls, 40 gel, 180 cement, 60/40 pos. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) P.O. Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 86



Irene Hoover
Notary Public

My Commission expires: _____

MAR 11 1986
3-11-86
CONSERVATION DIVISION

Form CP-4
Revised 01-84

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-179-05605-0000 ✓

Company- M.J. BOVE
Farm- Transue


No. 2

SEC. 18 T. 9
SE NW SE

R. 26W

Total Depth. 4042'
Comm. 9-24-63 Comp. 10-6-63
Shot or Treated.
Contractor. Emprie Drilling Co.
Issued. 1-25-64

County Sheridan
KANSAS



CASING:

8 5/8" 311' cem w/140 sx.
4 1/2" 4041' cem w/50 sx. & 600 Gal. Latex

Elevation. 2682' KB

Production. 40 BOPD, NW

Figures Indicate Bottom of Formations.

surface hole	316
shale & clay	500
shale & shells	1800
sand-shale-redbed	2260
shale	2268
Anhydrite	2301
shale	2340
shale-shells	2650
lime & shale	2724
shale & Shells	2850
lime & shale	2940
lime	3000
lime & shale	3185
lime	3235
lime & shale	3310
lime	3370
lime & shale	3650
lime	3710
shale & lime	3810
lime	4042 RTD
Total Depth	

TOPS: ELECTRIC LOG

Anhydrite	2267
Topeka	3596
Heebner	3775
Toronto	3799
Lansing	3816
Zone 2	3843
Zone 2A	3857
Zone 6	3947
Zone 6A	3972
Zone 7	3990
Zone 8	4010
Zone 9	4032