


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
245 North Water  
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 6 Twp. 9 Rge. 20W (W)  
Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Patton Oil Company  
Lease Name Clark #1 Well No.  
Office Address Hoisington, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 3/31/76 19  
Plugging completed 4/15/76 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4090 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	210	none
				4 1/2"	4088	1357

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3940' and ran 3 sacks cement. Shot pipe at 2500', 2320', 2123', 2024', 1929', 1836', 1737', 1640', 1543', 1448', 1350', pulled 42 joints of 4 1/2" casing. Pumped 3 sacks hulls, 17 sacks gel and 130 sacks cement, 50-50 pos, 6% gel.

PLUGGING COMPLETE. 4-21-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April 1976

My commission expires  
NOTARY PUBLIC  
MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

Margaret Melcher  
Notary Public.


15-179-30064-0000

# WELL LOG

COMPANY MURFIN DRILLING COMPANY  
 FARM CLARK NO. ONE  
 RIG. NO. 16  
 TOTAL DEPTH 4090'  
 COMM. 10-5-65 COMP. 10-17-65  
 SHOT OR TREATED  
 CONTRACTOR MURFIN DRILLING COMPANY  
 ISSUED 1-20-68

SEC. 6 T. 9S R. 28W  
 LOC. C NE NE

COUNTRY Sheridan-Kansas  
 KANSAS



CASING  
 20 10  
 15 8 5/8" @ 210' w/200 sx  
 12 6  
 13 5 4 1/2" @ 4088' 2/200 sx  
 FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 2721 KB

PRODUCTION ~~OK~~ DRY (MARM. SD)

20	Clay & Sand	TOPS: SCOUT	
1849	Shale	Anhydrite	2324
1895	Anhydrite	* B/Anhydrite	2360
2327	Shale	Topeka	3449
2365	Anhydrite	Heebner	3784
2670	Shale & Shells	Toronto	3807
2855	Shale & Lime	Lansing Kansas City	3824
2990	Shale-Lime	B/Kansas City	4052
3180	Shale & Lime	Marmaton sand	4065
3265	Lime & Shale		
3350	Lime-Shale		
3520	Lime & Shale		
3725	Lime		
3805	Lime-Shale		
4090	Lime		

State of KANSAS  
 County of SEDGWICK } ss:

I, James R. Daniels of the MURFIN DRILLING Company

upon oath state that the above and foregoing is a true and correct copy of the log of the CLARK # ONE well.

James R. Daniels  
 James R. Daniels



ADELA MIZENER, Notary Public  
 commission expires November 5, 1970

Adela Mizener  
 NOTARY PUBLIC

Subscribed and sworn to before me this 20th day of November 19 67