

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

2-3  
flo  
1183

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Sheridan SEC. 18 TWP. 9s RGE. 26 E/W  
Location as in quarters or footage from lines:  
SE SW SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner K.R.M. Petroleum Corporation  
Lease Name Transue Well No. 1  
Office Address 1900 Grant Street, Suite 300, Denver, Co 80203  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil Well  
Date Well Completed 1-23-59  
Application for plugging filed October, 1983  
Plugging commenced October 19, 1983  
Plugging completed October 20, 1983  
Reason for abandonment of well or producing formation depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hays District Office  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4030'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8"	250'	none
				5"	3020'	none
					KCL	

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Had to run tbg. in to plug well. Pumped 60 sxs. cmt., pulled 9 jts. tbg., pumped  
20 sxs. of gel in, pulled 40 jts., pumped 20 sxs. of gel in, pulled 40 jts. tbg.,  
pumped in 140 sxs. of cmt., wouldn't circ., pulled 41 jts. tbg. out, ran 29  
jts. back in, pumped 100 sxs. of cmt. & circd. Pulled tbg. out, filled surface  
pipe w/cmt.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pfeifer Well Service

STATE OF Colorado COUNTY OF Denver, ss.


Dwayne G. Krugman (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts; statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Dwayne G. Krugman  
1900 Grant St., Ste. 300 Denver, Co  
(Address) 80203

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 83

Dorothy T. Roberts  
Notary Public.

Dorothy T. Roberts  
1900 Grant St., Ste. 300  
Denver, Colorado 80203



WELL LOG ELEMENTS  
500 East Murdock,  
Wichita, Kansas

18-9-26W


15-179-00124

Company- SAUVAGE DRILLING CO.  
Farm- Transue No. 1

SEC. 18 T. 9 R. 23  
SE SW SE

Total Depth. 4030'  
Comm. 11-14-58 Comp. 1-23-59  
Shot or Treated.  
Contractor. Sauvage Drlg.  
Issued. 5-6-61

County Sheridan  
KANSAS



CASING:  
8" 250'  
5" 4020'

Elevation. 2679' RB

Production. 125 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE

TOPS: SCOUT	
Anhydrite	2257
Topeka	3596
Heebner	3783
Toronto	3803
Lansing	3823
Total Depth	4030

15-179-00124-0000