


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 17 Twp. 9 Rge. 26 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines E/2 SE NW

Lease Owner M. J. Bove Operating Co.

Lease Name Richards Well No. 1

Office Address 754 E. Wichita Ave., Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed Feb. 6, 19 68

Application for plugging filed Dec. 16, 19 68

Application for plugging approved Dec. 20, 19 68

Plugging commenced Dec. 20, 19 68

Plugging completed Dec. 30, 19 68

Reason for abandonment of well or producing formation \_\_\_\_\_

Decline to uneconomic Production level

If a producing well is abandoned, date of last production November 1, 19 68

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well WXX W. L. Nichols

Producing formation L-Kansas City Depth to top 3840 Bottom 4050 Total Depth of Well 4050 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
L-K. C.	Oil	3860	4030	8 5/8	304	none
				5 1/2	4050	1020

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to surface feet for each plug set.

Sanded from 4050' to 3750' with sand & chat. Dumped 5 Sacks cement.

Shot pipe at 1020' & pulled from hole. Pumped 5 sacks hulls, 4 sacks

Gel with 100 sacks 50/50 Pozmix, 20 sacks mud, 20 sacks cement

6 sacks mud and 10 sacks cement to the top of surface casing.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons

Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

E. T. Drube (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

754 E. Wichita Ave, Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January, 19 69

Ruth E. Miller

Notary Public.

My commission expires January 5, 1969

15-179-05643-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


**COPY**

Company. GRAHAM-MESSMAN-RINEHART OIL CO.  
Farm-Richards No. 1

SEC. 17 T. 9 R. 26W  
C E/2 NE NW

Total Depth. 4050  
Comm 2-15-51 Comp. 12-29-51  
Shot or Treated.  
Contractor. G. M. R. Oil Co.  
Issued. 2-28-53

County Sheridan  
KANSAS



Elevation. 2680 KB

CASING:  
8 5/8 set at 304' w/ 165 sx cement

Production 379 bbls. no water

Figures indicate Bottom of Formations.

shale	160
sand	185
shale & shells	1300
sand	1340
shale & shells	1765
anhydrite	1790
shale & red bed	1890
shale	2268
brown lime	2300
lime & shale	2425
shale	2630
lime & shale	3345
brown lime	3435
lime & shale	3600
brown lime	3725
lime & shale	3772
lime	4010
brown lime	4050
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS:	
Heebner	3797
Toronto	3818
Lansing	3836