


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 17 Twp. 9S Rge. 26W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SE NW  
Lease Owner M. J. Bove WZ RTKLL  
Lease Name Richards Well No. 2  
Office Address 754 E. Wichita Ave., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Injection  
Date well completed Wash down 10-28-63 19  
Application for plugging filed June 22, 1968 19  
Application for plugging approved June 24, 1968 19  
Plugging commenced 7-3-68 19  
Plugging completed 7-5-68 19  
Reason for abandonment of well or producing formation Unsatisfactory  
injection results  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Nichols  
Producing formation Inj-L-KC Depth to top 3880 Bottom 4043 Total Depth of Well 4059 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
L-K.C.	Injection	3880	4043		310' well 308'	none
				85/8		
				5 1/2	4059'	1100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4059 feet to surface feet for each plug set.

Sand from 4059 to 3500. Dumped 5 sacks cement. Shot pipe at 1100' & pulled from hole. Pumped 5 sacks hulls, 4 sacks gel, 100 sacks 50-50 pezmix, 20 sacks mud, 20 sacks cement, 6 sacks mud and 10 sacks cement cap.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnes & son  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
E. T. Drube (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. T. Drube*  
754 E. Wichita Ave., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 1968

*Ruth E. Miller*  
Notary Public.

My commission expires January 5, 1969