


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 17 Twp. 9 Rge. 26 (E) (W)  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Sauvage and Babcock  
Lease Name Richards Well No. 2  
Office Address Oberlin, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 6-8 1957  
Application for plugging filed 6-8 1957  
Application for plugging approved 6-8 1957  
Plugging commenced 6-8 1957  
Plugging completed 6-8 1957  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4060 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud on bottom -- pulled pipe to 1500 feet and circulated with heavy mud. Pulled pipe set plug 300 feet. Mixed 15 sx cement 1/2 sx hulls, through drill pipe and filled hole with heavy mud to 40 feet. Set plug. 10 sx cement 1/2 sx hulls. Filled surface casing to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sauvage and Dunn Drilling Company, Inc.  
Address Oberlin, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

SUBSCRIBED AND SWORN TO before me this 12<sup>th</sup> day of June, 1957

My commission expires May 17, 1959  
[Signature] Notary Public.

PLUGGING  
SEC. 17 T. 9 R. 26W  
BOOK PAGE 21 LINE 2

STATE CORPORATION COMMISSION  
6-17-57  
JUN 17 1957

15-179-19031-0000

Drillers Log

Operator: Sauvage & Dunn Drlg. Co.  
Farm Name: Richards  
Well No: #2  
Contractor: Sauvage & Dunn Drlg. Co., Inc.  
Rotary Commenced: May 23, 1957  
Rotary Completed: June 8, 1957

W/2 SE NW  
Location: Sec. 17, Twp. 9, Rge. 26  
Sheridan County, Kansas  
Casing Record: 310 ft. 8 5/8 csg  
163 sx cement

Figures denote bottom of formation

Cellar	5
Shale	490
Shale	1067
Shale and Shells	1483
Shale and Shells	1683
Shale and Shells	1768
Anhydrite	1808
Shale and Shells	1888
Shale	2250
Shale	2290
Anhydrite	2325
Red bet and Shale	2355
Shale and Shells	2438
Shale and Lime	2565
Shale and Lime	2670
Shale and Lime	2770
Shale and Lime	2845
Shale and Lime	2975
Shale and Lime	3050
Shale and Lime	3200
Shale and Lime	3255
Shale and Lime	3318
Shale and Lime	3375
Shale and Lime	3415
Shale and Lime	3468
Lime	3470
Lime	3535
Lime	3610
Lime	3700
Lime	3765
Lime	3793
Lime	3855
Lime	3873
Lime	3889
Lime and Shale	3936
Lime	3950
Lime and Shale	3994
Lime	4005
Lime and Shale	4060

State of Kansas  
County of Decatur

I hereby certify that the foregoing is, to the best of my knowledge and belief a full, true and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

*W. A. Sauvage*  
For Sauvage & Dunn Drlg. Co., Inc.

Subscribed to and sworn to before me, the undersigned, a Notary Public, this 12th day of June, 1957.

*W. A. Sauvage*  
Notary Public  
STATE OF KANSAS

My Commission expires May 17, 1959

PLUGGING  
SEC. 17 T. 9 26W  
PAGE 21 LINE 2

CONSE