


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sheridan County. Sec. 24 Twp. 9S Rge. 26W E/W  
Location as "NE/CNW<sup>1</sup>/SW<sup>1</sup>" or footage from lines \_\_\_\_\_  
NW NW SE

Lease Owner J. A. Allison  
Lease Name CORKE Well No. 1  
Office Address 300 W. Douglas, Suite 305, Wichita, Ks  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed March 21 19 80  
Application for plugging filed (verbally) March 21 19 80  
Application for plugging approved (verbally) March 21 19 80  
Plugging commenced March 21 19 80  
Plugging completed March 21 19 80  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4130'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

T.D. 4130'  
Set 1st plug at 1150' with 70 sacks  
2nd plug at 280' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks.

Cemented with 50/50 posmix, 6% gel.  
Plug was down at 1:00 p.m., March 21, 1980.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 80



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

CONTRACTOR'S WELL LOG

OPERATOR: J. A. Allison  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Corke #1  
 LOCATION: NW NW SE, Section 29, 9S-26W, Sheridan County, Kansas  
 SPUD DATE: March 14, 1980  
 COMPLETION DATE: March 21, 1980

0	133	Surface clay and shale
133	196	Sand
196	290	Sand and shale
290	1750	Shale and sand
1750	1765	Shale
1765	2285	Shale and sand
2285	2318	Anhydrite
2318	2395	Shale, lime and sand
2395	2631	Shale
2631	3160	Shale and lime
3160	3354	Lime and shale
3354	3514	Lime
3514	3695	Shale and lime
3695	3903	Lime and shale
3903	3943	Shale and lime
3943	4045	Lime
4045	4130	Shale and lime
	4130	Rotary Total Depth

Spud hole at 2:30 p.m., March 14, 1980. Drilled 290' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 20# casing. (Tally 282'). Set at 289' with 225 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:00 p.m., March 14, 1980.

T.D. 4130'. Set 1st plug at 1150' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 1:00 p.m., March 21, 1980.

SAMPLE TOPS:

Anhydrite 2285'  
 B/Anhydrite 2318'

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 31 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Corke #1, NW NW SE, Section 29-9S-26W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.  
 BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 27th day of March, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.