

6 030646

15-195-20875-00-00

API NUMBER 15-195-20,875-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

CSE NW, SEC. 6, T. 11 S, R. 23 W

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name COMEAU Well # 1

Operator: F & M OIL CO. INC.

County TREGO 128.02

Name & Address 422 UNION CENTER

Well Total Depth 3939 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 213'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS 67524

Company to plug at: Hour: PM Day: 8 Month: 1 Year: 19 86

Plugging proposal received from MILLARD KELSO

(company name) KELSO CASING (phone) \_\_\_\_\_

were: 8 5/8 @ 213 w/1604 4 1/2 @ 3937 w/125 PERF 3660 - 3837 PBDT 3889'

ORDER SAND AND COM. CNT. SHOOT & STRIP. CASING. ORDER 180SX.

60/40 P226 GEL 3 1/2" 40SX GEL, 4" SX. HULLS 8 5/8 W.P. B.J. TITAN CNT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1: PM Day: 8 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBDT TO 3600' SPOT 4SX. DUSTON SAND

w/BAILER. SHOT & RECOVERED 2707' OF CASING.

MIX. & Pump DOWN 8 5/8 3SX. HULLS - 25 SX. GEL. 100SX. CNT + 1SX. HULLS

15 SX. GEL. 8 5/8 W.P. 80SX. CNT. MAX. PSI 800# CLOSE IN PSI 400#

PLUG. COMPLETE

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 30 1986

INV. NO. 12169

RECEIVED STATE CORPORATION COMMISSION 1-21-1986 JAN 21 1986

Signed Carl Goodrow (TECHNICIAN)

40 1-17-86 mm