

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22021-00-00
Spot: E2E2W2, Sec/Twnshp/Rge: 10-11S-23W
2640 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: DENISON Well Number: 5
County: TREGO Total Vertical Depth: 3800 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

Conductor Pipe: Size feet: 8 1/23.50
Surface Casing: Size 8.625 feet: 212 150 SX CMT
Production: Size 4.5 feet: 3797 450 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/10/2002 10:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: MIKE MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs 3696'-3699'; 3725'-3728'; 3737'-3740'.
Pull rods and pump tubing stuck in the hole - shot off at 3440' leaving 334' in hole.
Fluid level at 3450'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/10/2002 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged up to backside with a swedge and pumped 25 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 400#.
Rigged up to casing and pumped 180 sxs 60/40 pozmix with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Job completed.

RECEIVED
7-15-2002
JUL 15 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #11660.

Plugged through: CSG

District: 04

Signed *Pat Staab*

(TECHNICIAN)

INVOICED

DATE 7-19-02

INV. NO. 2003060071

Form CP-2/3

JUL 10 2002

SHIELDS OIL PRODUCERS, INC
RUSSELL, KS 67665

10-11 -23W
C E/2 E/2 W/2


#5 DENISON

site: 5 N & 1/2 E OF WAKEENEY, KS
contr: SHIELDS DRILLING COMPANY, INC

cty: TREGO
field: WAKEENEY

API 15-195-22021

geol: JERRY HONAS
lr date 05/31/89 spd date 06/09/89 drlg comp 06/25/89 card issued 08/09/89 last revised 08/09/89



ELV: 2273 KB LOG	depth/datum
tops.....	1742 +531
ANH.....	1799 +474
B/ANH.....	3487 -1214
HEEB.....	3507 -1234
TOR.....	3522 -1249
LANS.....	3746 -1473
BKC.....	3774 -1501
PBTD.....	3800 -1527
RTD.....	

IP status:

OIL, P 20 BO & 60 BWPD, LKC 3696-3740 OA,
CSG: 8-5/8" 212 / 150 SX, 4-1/2" 3797 / 450 SX
NO CORES
DST (1) 3688-3735 (LKC), / 30-45-45-60, WB INCR TO
FB, 340' GIP, REC 200' HOCWM, 60' SLJ OCMW ISIP
535# FSIP 504# IFP 94# -105# FFP 136# -147#
MICT - CO, PB 3774 TD, PF (LKC) 3696-3699, 3725-
3728, -3737-3740, W / 2 SPF, AC 1000 GAL, TST 3 BFPH
(80% OIL), RE-AC 3000 GAL, TST 10 BFPH (35% OIL) / 4
HRS, SET 2" TBG AT 3770, NO PKR, POP, P 20 BO & 60
BWPD (GR 40), 7/20/89

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS