

To: 6 090368
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-14-88 163
API NUMBER 15- 195-21,966-00-00
NW, SEC. 11, T 11 S, R 23 W/O
3630 feet from S section line
4465 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3667

Lease Name McCall A Well # 2

Operator: Presley Petroleum Co. d/b/a
Name & Address Source Petroleum
910 Century Plaza Bldg.
Wichita, Kansas 67202

County Trego 129.09
Well Total Depth 3972 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A X

Other well as hereinafter indicated _____

Plugging Contractor Lobo Drilling Co. License Number 5864

Address Great Bend, Kansas

Company to plug at: Hour: _____ Day: 11 Month: March Year: 19 88

Plugging proposal received from Irwin Neighbors

(company name) Lobo Drilling (phone) _____

were: Order 205 sks 60/40 Poz 6% Gel and 8 5/8" wiper plug.

Spot all plugs through drill pipe w/heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30PM Day: 14 Month: March Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3939' w/20 sks

2nd plug at 1720' w/20 sks

3rd plug at 890' w/100 sks

4th plug at 265' w/40 sks

5th plug at 40' w/10 sks

15 sks in rat hole

Remarks: Elevation 2236' Anhydrite 1714' Arbuckle Yes CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

I (Edwin A. Schumacher) did not observe this plugging.

Signed Edwin A. Schumacher
(TECHNICIAN)
Edwin A. Schumacher

DATE 4-27-88

INV. NO. 20489