

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21321-00-01

Spot: ^{dw} SESENE

Sec/Twnshp/Rge: 4-17S-12W

3091 feet from S Section Line,

637 feet from E Section Line

Lease Name: LANG

Well #: B-1

County: BARTON

Total Vertical Depth: 3315 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3313	0	w/125 sxs cmt
SURF	8.625	288	0	w/175 sxs cmt

107.74

Well Type: SWD

UIC Docket No: D25552.0

Date/Time to Plug: 02/20/2009 1:00 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: KEVIN WILES SR

Company: AMERICAN WARRIOR, INC.

Phone: (620) 272-1023

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 4% gel.

Well is a SWD. Has 4 1/2" casing with 2 3/8" tubing cemented in 4 1/2".

Tubing is plugged with trash - ran 1" tubing to 1500'.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/20/2009 6:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran 1" tubing to 1500'. Tied to tubing - pumped 20 sxs cement with circulation.
Pulled to 700' - pumped 75 sxs - no circulation - ran out of cement.
Ordered an additional 150 sxs cement.
Ran 1" tubing to 500' - pumped 45 sxs cement.
Pulled tubing - pumped 20 sxs cement. Max. P.S.I. 300#. Shut in.
02/23/2009 - Down 300' - called operator - will top off.

Perfs:

Top	Bot	Thru	Comments
3312	3315		

INVOICED
DATE 3-31-09
INV. NO. 2009061350

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: SWIFT SERVICES CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

MAR 02 2009

BERGMAN OIL CO.
 520 UNION CENTER
 WICHITA, KS.
 CONTR BERGMAN DRLG., INC. #2 LANG B-1
 CTY BARTON
 4-17-12W
 APPX SE SE NE

GEOL _____ FIELD ODIN

E 1856 KB CM 1/15/78 CARD ISSUED 10/12/78 OIL WELL
 ARB - INTV UNKNOWN

+	+	+
+	+	+
+	+	+

API 15-009-21,321

SMP	TOPS	DEPTH	DATUM
SC		728	+1128
B SC		753	+1103
KC		3200	-1344
ARB		3267	-1411
RTD		3315	-1459

8-5/8" 288/175 SX, 4 1/2" 3312 1/2 /125 SX
 MICT - CO, TSTD ARB-INTERVAL UNKNOWN-
 OIL WELL-NO OTHER INFO RELEASED BY
 OPERATOR

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS