

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24136-00-00  
Spot: SESW Sec/Twnshp/Rge: 13-18S-21W  
640 feet from S Section Line, 1960 feet from W Section Line  
Lease Name: WELLS Well #: 2-13  
County: NESS Total Vertical Depth: 2290 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2289	0	WITH 285 SX CMT
SURF	8.625	222		WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2009 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

74.43

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/02/2009 11:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CEDAR HILLS FLOWING @ 20 BWPH. RAN TBG TO 2210' & PUMPED 35 SX CMT W/100# HULLS. PULLED TBG TO 1310' & PUMPED 125 SX CMT W/400# HULLS CIRCULATING TO SURFACE UP 5 1/2". PULLED TBG OUT OF HOLE. FILLED 5 1/2" WITH 25 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 250# WITH 15 SX CMT. BLEW OUT BRADEN HEAD.

Perfs:

Top	Bot	Thru	Comments
2238	2241		
2190	2194		

**INVOICED**  
DATE 3-31-09  
INV. NO. 2009061350

**RECEIVED**

**MAR 13 2009**

**KCC WICHITA**

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

**RECEIVED**  
MAR 12 2009  
KCC DODGE CITY

Signed Richard W. Lacey  
(TECHNICIAN)