

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00538-00-00
Spot: NE Sec/Twnshp/Rge: 2-35S-34W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: PRINTZ A Well #: 1
County: SEWARD Total Vertical Depth: 2760 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2759	495	WITH 620 SX CMT
SURF	8.625	691		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2009 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

89.70

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2009 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 300# HULLS & 20 SX CMT @ 2658' THROUGH TBG. PUMP 20 SX CMT @ 1650'. NO CIRCULATION. FREE POINT 4 1/2" CASING @ 525'. SHOOT OFF CASING @ 495' & TOOH. TIH WITH TBG TO 750' & SPOT 50 SX CMT. PUMP 10 SX CMT AT 40'-0'.

Perfs:

Top	Bot	Thru	Comments
2658	2738		

INVOICED
DATE 3-31-09
INV. NO. 2009061351

RECEIVED
MAR 13 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

KCC WICHITA

Plugged through: TBG

District: 01

RECEIVED

FEB 25 2009

KCC DODGE CITY

Signed _____

Ken Jehlik

(TECHNICIAN)