

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22667-00-01

Spot: NESWSE

Sec/Twnshp/Rge: 17-15S-13W

1009 feet from S Section Line,

1730 feet from E Section Line

Lease Name: TOM SELLENS

Well #: 12

County: RUSSELL

Total Vertical Depth: 3389 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380
WICHITA, KS 67208

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 5.5 | 3389 | 0 | w/290 sxs cmt |
| SURF | 8.625 | 853 | 0 | w/350 sxs cmt |

110.14

Well Type: EOR

UIC Docket No: E07607.17

Date/Time to Plug: 03/03/2009 10:00 AM

Plug Co. License No.: 5363

Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO, INC.

Phone: (316) 265-3311

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel. Perf at 1480' and 830'.

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/03/2009 2:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3200' - pumped 50 sxs cement with 250# hulls.
Pulled tubing to 2700' - pumped 13 sxs gel.
Pulled tubing to 1480' - pumped 50 sxs cement with 250# hulls.
Pulled to 1000' - pumped 300 sxs cement.
Pulled tubing out of well - hooked up to casing and pumped 70 sxs cement - circulated out the braden head.
Max. P.S.I. 200#.

INVOICED
DATE 3-31-09
INV. NO. 2009061352

Remarks: ALLIED CEMENTING COMPANY-TICKET #34963A.

Plugged through: TBG

RECEIVED
MAR 13 2009
KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

MAR 05 2009

TERRA RESOURCES, INC.

P.O. BOX 839

#12 TOM SELLENS

17-15-13W

NE SW SE


OKLAHOMA CITY, OK 73101

CONTR ALLEN DRILLING

CTY RUSSELL

GEOL MIKE FLETCHER

FIELD TRAPP



ELV 1859 KB SPD 10/3/85 CARD ISSUED 11/7/85 IP P 18 B0 & 123 BWPD
.1854.5GL LKC 3062-3140 OA

| SMP | Tops | Depth/Datum |
|-------|-------|-------------|
| DOVER | | 2424- 565 |
| TARK | | 2461- 602 |
| HOW | | 2672- 813 |
| SEV | | 2721- 862 |
| TOP | | 2737- 878 |
| HEEB | | 2970-1111 |
| TOR | | 2987-1128 |
| LANS | | 3041-1182 |
| MARM | | 3265-1406 |
| ARB | | 3315-1456 |
| RTD | | 3390-1531 |

API 15-167-22,667

8 5/8 " 853 / 350SX, 5 1/2 " 3389 / 290SX

NO CORES OR DSTS

MICT - CO, PF (LKC G) 3138-40, W / 4 SPF, AC 200G (15%

MCA), SWB 100' FL (37% OIL), RE-AC 800G (28% NE), SWB 250'

FL (28% OIL), PF (LKC C) 3062-82, W / 2 SPF, AC 2000G (15%

MCA), SWB 250' FL (12% OIL), RE-AC 4000G (28% NE), SWB

325' FL (14% OIL), POP, P 18 B0 & 123 BWPD

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS